4	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaiton.(Page No.17, Item No.4.31)								
	Basic Rate=		251.00						
	Add A.W.8%=		20.08						
	Total=		271.08						
	1st A Cross	2	4	132.00		0.60	633.60		
		sqm					633.60	271.08	171756.29
5	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed cement concrete for beams,columns, staircase and roof with M20 RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) (Page No.19 Item No. 4.49.1)								
	Basic Rate=		5989.00						
	Add A.W.8%=		479.12						
	Total=		6468.12						
	Kerb poration								
	1st A Cross		2	132.00	0.30	0.075	5.94		
	Bedslab				Total qty A		5.94		
	1st A Cross	1	2	132.00	1.00	0.15	39.60		
	Side wall								
	1st A Cross	2	2	132.00	0.15	0.60	47.52		
					Total qty B		87.12		
					Total qtyA+B		93.06		
		cum					93.06	6468.12	601923.25
6	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for Bars Fe 415 R.C.C** work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3(Page No.19 Item No. 4.46.1)								
	Basic Rate=		6834.00						
	Add A.W.8%=		546.72						
	Total=		7380.72						
	qty 65kg/cum		174.24cumX65kg/cum				56.63		
		qtl					56.63	7380.72	417955.41
7	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete.(Page No.28 Item No.5.29.1) of size 450 x 200 x 400 mm								417970.17
	Basic Rate=		~~268.00~~	293					
	Add A.W.8%=		~~21.44~~	23.44					
	Total=		~~289.44~~	316.44		242.00			
	1st A Cross	1	2	~~132.00~~		~~264.00~~			
				121.00	0.45	~~264.00~~			
						242.00			